Sl. No.	Items of work	Unit	Quantity
2	Removing 2½" C. I. pipes 1420' of 9' lengths ...	Cwt.	158
3	Removing 1½" G. I. pipes	R.ft.	300
4	Cleaning do	,,	300
5	Making lead joints 2½" C. I. pipe including laying and jointing complete with cuts wherever necessary.	No.	15
6	Making cement joints to 2½" pipes including laying and jointing with cuts wherever necessary.	,,	143
7	Laying and jointing 1½" G. I. pipes including cutting and threading without earthwork.	R.ft.	300
	Laying 3" C. I. pipe in Maharaja Road, Robertsonpet.		
1	Earthwork excavation, refilling, tamping and bringing the road surface to original condition.	Cyd.	300
2	C. I. cuts 3"	No.	2
3	Removing 3" C. I. pipes at connection	Cwt.	2
4	Making lead joints to 3" C. I. pipe including laying and jointing complete with cuts wherever necessary.	No.	14
5	Making cement joints to 3" G. I. pipes including laying and jointing complete with cuts wherever necessary.	,,	130
6	Fixing C. I. valves 3" with rubber insertion ...	,,	2
7	Removing 1½" G. I. pipe	R.ft.	400
	Laying 5" C. I. Pipes from the Tank to Carr Road in Robertsonpet.		
1	Earthwork excavation, refilling, tamping and bringing the road surface to original condition. ...	Cyd.	628
2	Making 5" lead joints.	No.	25
3	5" C. I. cuts	Nos.	2
4	5" Cement joints	No.	210
5	Fixing 5" C. I. valve	,,	1
6	Constructing valve cistern with shutters	,,	1

B. R. GARUDACHAR,
Executive Sanitary Engineer.

BANGALORE DIVISION.

Notification dated 25th March 1933.

Notice is hereby given that the sealed quotations will be received at the Office of the Executive Engineer, Bangalore Division, up to 2 P.M. on 24th April 1933 for "Constructing a New Tank near Kannaikan Agrahahar village of Anekal Taluk". An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1934.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office, Bangalore Division Bangalore, between the hours of 11 A.M. and 5 P.M., on all office days.

3. Tenders should be submitted on printed forms, which may be obtained from the Executive Engineer. The quotations should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 250 in cash as earnest money and be superscribed "Tender for Constructing a New Tank near Kannaikan Agrahara Village of Anekal Taluk" in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Charges on account of scaffolding materials, implements for setting out, barricading, clearing site, supply of water, etc. that may be found necessary during execution will not be paid for separately, but should be borne by the contractor.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of disputes about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer, Bangalore Division, will be final and legally binding.

12. Quotations must be shown in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimate rate will not be accepted.

13. Any tender containing a conditional clause contrary to these requirements or making stipulations not provided for either in this advertisement or the abstract quantity will summarily rejected.

Abstract estimate for constructing a New Tank near Kannaikan Agrahara Village of Anekal Taluk.

No.	Item of work	Unit	Rs. a. p.	Quantity	Remarks
	Bund : R. L. 59·00 Top width 41' and 6' at Halla Portion.				
1	Clearing with roots	Grades		5	
2	Cutting steps and grips for the seat of bund	,,		5	
3	Earthwork raising bund including watering and tamping lead and lift.	C.yds.		10,244	
4	Gravel backing to revetment ...	... ,,		323	
5	New stone revetment with jelly backing and wedging.	,,		1,033	
6	Turfing	Syds.		2,131	
7	Burnt brick in surki mortar	C.ft.		145	
8	Puddle wall with good clay mixed with pit gravel.	C.yds.		116	
9	Providing grade stone including zero stone..	Each		6	
10	Do index stone	,,		6	
11	Do B. M. stone	,,		2	
12	Do register and date stone ...	,,		1	
13	Do gauge stone	,,		1	
	Masonry sluice R. L. 42·00.				
1	Earthwork cut opening the ground and refilling.	C.yds.		190	
2	Earthwork excavation	,,		22	
3	Concrete in surki mortar	C.ft.		218	
4	Burnt brick in surki mortar	,,		1,051	
5	Burnt stone slabs 6" thick dressed ...	S.ft.		399	
6	Pointing with surki mortar ...	Sqr.		1·00	
7	Plastering with surki mortar ...	,,		3·50	
8	Cutting holes in slabls	Each		3	
9	Orifice slab	,,		1	
10	Providing plug with iron rod including locking arrangements.	,,		1	
	Waste weir R. L. 56·00 length 104 feet.				
1	Clearing draft and approach and using to bund including lead and lift.	C.yds.		1,000	
2	Earthwork excavation	,,		96	
3	Rough stone work new	,,		32	
4	Rough stone retaining wall	,,		139	

H. F. MARBER,